

15-163-20242-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 11 Twp. 9S Rge. 18W (E) _____ (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Landes Exploration Co. and Sentinel Resources Corp.
Lease Name O'Brien Well No. 1
Office Address P. O. Box 867, Magnolia, Arkansas 71753
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 22 19 69
Application for plugging filed August 22 19 69
Application for plugging approved August 22 19 69
Plugging commenced August 22 19 69
Plugging completed August 22 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas 67601
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3590 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	215'	8 5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug: 660'/70 sacks cement
210'/20 sacks cement
40'/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1969
CONSERVATION DIVISION
Wichita, Kansas

8-28-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.
Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
D. L. Hellar, President of Hellar Drlg. Co. Inc. (Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar D. L. Hellar, President
339 Union Center Bldg., Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 26th day of August, 19 69
Catherine Darcey
Catherine Darcey - Notary Public.



DRILLER'S LOG

COMPANY: Landes Exploration Co. and Sentinel Resources Corp.,
 P. O. Box 867, Magnolia, Arkansas 71753

CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202

LEASE: #1 O'Brien

LOCATION: NW NW SE 11-9S-18W, Rooks County, Kansas

COMMENCED: August 15, 1969

COMPLETED: August 22, 1969

CASING: Set 8 5/8" Surface Casing @ 215'/150 sacks cement

0-43	Post Rock
43-217	Post Rock & Shale
217-1165	Shale, Shells & Sand
1165-1440	Shale
1440-1463	Anhydrite
1463-1560	Red Bed & Shale
1560-2150	Salt Section & Ft. Riley
2150-2319	Ft. Riley
2319-2890	Lime & Shale
2890-3101	Lime & Shale - Topeka Lime
3101-3260	Lime & Shale
3260-3440	Lime & Shale - L.-K.C.
3440-3520	K. C. Lime & Cong. Section - B. K.C.
3520-3590	Cong. & Arbuckle
3590	Rotary Total Depth

D & A

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 28 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 8-28-69

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 O'Brien, located in NW NW SE 11-9S-18W, Rooks County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 26th day of August, 1969.

Catherine Dargay
 Notary Public - Catherine Dargay

My Commission Expires: March 25, 1972.

