

15-163-00708-00-00


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rooks County. Sec. 14 Twp. 9 Rge. 18 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NW SE
Lease Owner J. F. Darby Oil Company
Lease Name Van Dyke Well No. 1
Office Address 1807 Philtower Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-29-54 19
Application for plugging filed 11-29-54 19
Application for plugging approved 11-29-54 19
Plugging commenced 11-29-54 19
Plugging completed 11-29-54 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3647 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water	3628		8-5/8	193	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy Mud to bottom of Surface Casing
1st Plug set at bottom of Surface Casing & Cemented with 15 sacks of Cement
Hole filled with mud to 40 feet
2nd plug set at 40 feet cemented with 10 sacks of cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Iron Drilling Co.
Address 1206 Philtower Bldg., Tulsa, Okla.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
J. L. Stackpole (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J L Stackpole
Tulsa, Okla.
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of December, 19 54
My commission expires Feb. 28, 1956



RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1954
12-9-54
Notary Public.
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 14-9-11W
BOOK PAGE 81 LINE 18

DRILLING RECORD

15-163-00708-00-00

Well No. 1 Van Dyke
NE NW SE Sec 14-9S-18W
Rocks County, Kans.

Casing Record

197' of 8-5/8" OD Surface Casing
cemented w/ 125 sacks.

Well Commenced 11/18/54
Drilling Commenced 11/19/54
Drilling Completed 11/29/54
Work Completed 11/29/54

No Oil String - Dry Hole

WELL LOG

Surface Shale	0 to 192
Shale	193 to 590
Shale & Sand	590 to 740
Shale & Shells	740 to 1000
Sand	1000 to 1180
Red Bed	1180 to 1360
Shale & Shells	1360 to 1475
Anhydrite	1475 to 1510
Shale & Shells	1510 to 1825
Shale & Salt	1825 to 1920
Shale & Shells	1920 to 2125
Shale & Lime	2125 to 2265
Lime & Shale	2265 to 2635
Lime	2635 to 2710
Lime & Shale	2710 to 2935
Lime	2935 to 2976
Shale & Lime	2976 to 3240
Lime	3240 to 3582
Chert	3582 to 3602
Simp. Dolim.	3602 to 3605
Cherty Conglomerate	3605 to 3628
Arbuckle	3628 to 3647 TD

PLUGGING
 FILE SEC 14 T 9 R 18W
 BOOK PAGE 81 LINE 18

12-9-54