

15-163-00976-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 15 Twp. 9 Rge. 18 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner C-G Drilling Co. & Oil Trading Associates, Inc.
Lease Name Toelkes Well No. 1
Office Address 107 Rule Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 2 19 56
Application for plugging filed September 2 19 56
Application for plugging approved September 2 19 56
Plugging commenced September 3 19 56
Plugging completed September 3 19 56
Reason for abandonment of well or producing formation Too low structurally

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3590 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	177'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 172'. Set plug.
Put in 1/2 sack of Hulls and 15 sacks of cement.
Filled with heavy mud up to 40'. Set plug.
Filled to top with 1/2 sack of Hulls and 10
sacks of Cement.

FILED
STATE OF KANSAS

9-7-56


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jay H. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
107 Rule Bldg.
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 19 56

Vicky Jacobs
Vicky Jacobs Notary Public.



PLUGGING
FILE SEC 15 T 9 R 18 W
BOOK PAGE 96 LINE 3

15-163-00976-00-00

CONTRACTOR'S WELL LOG

OPERATOR C-G DRILLING CO. & OIL TRADING ASSOCIATES, INC. WELL NAME TOELKES #1

LOCATION NE/4 NE/4 SE/4 SECTION 15-9S-18W RIG NO. 1

COUNTY _____ ROOKS STATE KANSAS

COMMENCEMENT DATE AUGUST 24, 1956 COMPLETION DATE SEPTEMBER 2, 1956

LOG OF WELL

Elevation 2074' rotary bushing.
All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	45	Sand		
45	177	Sand-Shale		
177	900	Sand-Shale		
900	1120	Sand		
1120	1401	Red Bed		
1401	1440	Anhydrite		
1440	1610	Shale		
1610	2040	Shale-Shells		
2040	2185	Lime-Shale		
2185	2260	Lime-Shale		
2260	2370	Lime-Shale		
2370	2495	Lime-Shale		
2495	2610	Lime-Shale	0° - 2500	
2610	2730	Lime-Shale		
2730	2840	Lime-Shale	0° - 2750	
2840	3000	Lime-Shale	0° - 3000	
3000	3120	Lime-Shale		
3120	3245	Lime-Shale		
3245	3305	Lime-Shale	0° - 3250	
3305	3445	Lime-Shale		
3445	3530	Lime-Shale	0° - 3500	
3530	3580	Lime-Shale		
3580	3590	Lime		

9-7-56

DST 3514-35'

CASING LEFT IN HOLE AFTER COMPLETION

Set 177' (9 jts.) 8-5/8" OD Surface Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay W. Galloway
Jay W. Galloway

Subscribed and sworn to before me on this 5th day of September, 1956.

My commission expires:
May 20, 1959

Vicky Jacobs
Vicky Jacobs, Notary Public

PLUGGING
FILE SEC 15 : 9 R 18W
BOOK PAGE 96 LINE 3