

15-065-00830-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Graham County, Sec. 15 Twp. 9S Rge. 22W (X) (W)

Location as "NE/CNW%SW%" or footage from lines SW 1/4 SW 1/4 NE 1/4

Lease Owner Leben Drilling, Inc.

Lease Name Justus Well No. 1

Office Address 905 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-1-59 19

Application for plugging filed 1-1-59 19

Application for plugging approved 1-1-59 19


Plugging commenced 1-1-59 19

Plugging completed 1-1-59 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3995' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	219'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug @ 600' with 20 sacks cement  
2nd plug @ 225' with 20 sacks cement  
top plug @ 40' with 1/4 sack hulls & 10 sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 7 1959  
CONSERVATION DIVISION  
Wichita, Kansas

1-7-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

L. Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin  
905 Central Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of January, 19 59

My commission expires June 17, 1961

Ruth N. Benjamin  
Notary Public.

PLUGGING  
FILE SEC 15 T. 9 R. 22W  
BOOK PAGE 10 LINE 12

DRILLER'S LOG

COMPANY: LEBEN DRILLING, INC.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: JUSTUS #1  
 LOCATION: SW $\frac{1}{4}$  SW $\frac{1}{4}$  NE $\frac{1}{4}$  SEC. 15-9S-22W  
 GRAHAM COUNTY, KANSAS  
 COMMENCED: 12-22-58  
 COMPLETED: 1-1-59

0	40	Surface Clay	
40	229	Shale & Shells	<u>TOPS:</u>
229	900	Shale & Shells	Anhydrite 1837
900	975	Shale & Sand	Heebner 3538
975	1380	Shale, Shells & Sand	Toronto 3563
1380	1560	Sand	Lans.K.C. 3575
1560	1837	Shale, Shells & Redbed	Bs. K.C. 3788
1837	1880	Anhydrite	Marmaton Cht. 3860
1880	2225	Shale & Shells	Conglomerate 3935
2225	3576	Shale & Lime	Arbuckle 3974
3576	3793	Lime	Elevation 2319 K.B.
3793	3925	Shale & Lime	
3925	3935	Chert	
3935	3974	Chert & Shale	
3974	3995	Dolomite	
	<u>3995</u>	<u>Rotary Total Depth</u>	

Set 219' of 8 5/8" surface casing with 140 sacks cement & 2% CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Justus #1, located SW $\frac{1}{4}$  SW $\frac{1}{4}$  NE $\frac{1}{4}$  of Section 15, Township 9 South, Range 22 West, Graham County, Kansas, as reflected by the files of Leben Drilling, Inc.

**RECEIVED**  
 STATE CORPORATION COMMISSION

JAN 7 1959

CONSERVATION DIVISION  
 Wichita, Kansas

LEBEN DRILLING, INC.

Frank Hamlin  
 Frank Hamlin

STATE OF KANSAS )  
 COUNTY OF SEDGWICK )

ss:

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 5th day of January, 1959.

Ruth N. Benjamin  
 Ruth N. Benjamin - Notary Public

My commission expires:

June 17, 1961

**PLUGGING**  
 FILE SEC 15 T. 9 R22W  
 BOOK PAGE 10 LINE 12