

15-065-20728-00-00


FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Graham County, Sec. 18 Twp. 9S Rge. 22W (E) (W)

Location as "NE/CNWSW" or footage from lines S/2 SE SE
Lease Owner Okmar Oil Company
Lease Name Willis Well No. 2
Office Address 1130 Vickers-KSB&T Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed January 21 19 75
Application for plugging filed January 21 19 75
Application for plugging approved January 21 19 75
Plugging commenced January 21 19 75
Plugging completed January 21 19 75
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W.L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3895' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	270'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug #1 @ 1070' w/70 sx. cmt.
Plug #2 @ 260' w/20 sx. cmt.
Plug #3 @ 40' w/10 sx. cmt. & 1/2 sk. hulls.
Cmt. was 50-50 pozmix, 6% gel.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 19 75

My commission expires December 28, 1977

D'Ann Drennan
Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1975
CONSERVATION DIVISION
Wichita, Kansas

3-24-75

19-065-20728-00-00

DRILLERS LOG

No. 2 Well

CASING RECORD:	COMPANY:	Okmar Oil Co.	DESCRIPTION:
8-5/8" @ 270' w/150 sx. cmt.	CONTRACTOR:	Red Tiger Drilling Co.	S/2 SE SE 18-9S-22W Graham County, Kansas
TOTAL DEPTH: 3895'	COMMENCED:	1-12-75	COMPLETED:
	COMPLETED:	1-21-75	

ELEVATION: 2408' K.B.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock & Shale	0	210	
Shale	210	760	
Shale & Sand	760	1325	
Shale, Clay & Shells	1325	1780	
Shale	1780	1952	
Anhydrite	1952	1994	
Shale	1994	2520	
Shale & Lime	2520	2900	
Shale	2900	3200	
Lime & Shale	3200	3445	
Lime	3445	3895	

RECEIVED
STATE COMMISSION
MAR 7 1975
3-7-75

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 23rd day of January, 1975.

Diane Drennan
Notary Public

My Commission Expires:

December 28, 1977

