

15-065-21927-00-00

API NUMBER 15-065-21,927

LEASE NAME Rice Trust

WELL NUMBER 1

SPOT LOCATION NE NE NW

SEC. 19 TWP. 9 RGE. 22 ~~XXXX~~(W)

COUNTY Graham

Date Well Completed 5-11-84

Plugging Commenced 5-11-84

Plugging Completed 5-11-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Viking Resources

ADDRESS 217 E. William Wichita, Ks. 67202

PHONE # (316) 262-2502 OPERATORS LICENSE NO. 5011

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6

Is ACO-1 filled? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. 3920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	246'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Spotted 20 sx. cement @ 1990' thru drill pipe.

Spotted 100 sx. cement @ 1176' thru drill pipe.

Spotted 40 sx. cement @ 300' thru drill pipe.

Spotted 10 sx. cement @ 10' thru drill pipe.

Spotted 10 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc.

License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas

COUNTY OF Sedgwick, ss.

Ernest Sifford


(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ernest Sifford

(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 24 day of May, 1984




David F. Jamis, Notary Public

My Commission expires:

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1984
5-31-84
CONSERVATION DIVISION
Wichita, Kansas



15-065-21927-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Viking Resources 217 E. William, Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Rice Trust Well No. 1
 Sec. 19 T. 9S R. 22W Spot NE NE NW
 County Graham State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 246' with 170 sx. 3%cc
2%gel
 Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 3920'
 Drilling Commenced 5-5-84 Drilling Completed 5-11-84

Formation	From	To	Tops
Cellar	0	7	
Clay, Shale	7	366	
Shale, Sand	366	1426	
Shale	1426	1510	
Sand	1510	1730	
Shale	1730	1985	
Anhydrite	1985	2019	
Shale, Lime	2019	3460	
Lime, Shale	3460	3615	
Shale, Lime	3615	3750	
Lime, Shale	3750	3835	
Lime	3835	3920	

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1984

CONSERVATION DIVISION
Wichita, Kansas

5-31-84