

15-065-00244-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Section Plat grid with 4 columns and 4 rows.

Locate well correctly on above Section Plat

Graham County. Sec. 22 Twp. 9S Rge. 22 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE $\frac{1}{4}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$
Lease Owner Barnett Drilling, Inc., et al
Lease Name Justus Well No. 1
Office Address 623 First Nat'l. Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 18, 19 51
Application for plugging filed July 18, 19 51
Application for plugging approved July 18, 19 51
Plugging commenced July 18, 19 51
Plugging completed July 18, 19 51
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Surface Casing, 0, 166 Ft., 8 5/8", 166 Ft., None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3,975 feet to 166 feet. Set wooden plug at 165 feet. Filled hole with 1 sack of hulls and 15 sacks of cement to 116 feet. Filled with heavy mud to 35 feet and set top wooden plug at 35 feet. Dumped 1 sack of hulls on plug and filled to bottom of cellar with 10 sacks of cement.

RECEIVED
COMMISSION
JUL 27 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Barnett Drilling, Inc. 7-27-51
Address 623 First National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. E. Cruce (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Cruce

623 First National Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 26th day of July, 19 51

Adelaide Olivier Notary Public.

My commission expires May 12, 19 55

23-5091-9 8-50-10M

PLUGGING
FILE SEC 28 T 9 R
BOOK PAGE 27 LINE 9

15-065-00244-00-00

BARNETT DRILLING, INC., ET AL
LOG OF JUSTUS WELL NO. 1
NE¹/₄ NE¹/₄ NE¹/₄ SECTION 22-9S-22W, GRAHAM COUNTY, KANSAS

DATE COMMENCED: July 4, 1951

DATE COMPLETED: July 18, 1951

Formation	From	To	Remarks
Sand	0	20'	
Surface Clay	20'	110'	
Sand	110'	125'	
Shale and Shells	125'	150'	
Shale	150'	166'	
			Set 8 5/8" Surface Pipe @ 166 feet; cemented with 125 sacks.
Shale and Shells	166'	1,250'	
Sand	1,250'	1,450'	
Shale and Shells	1,450'	1,780'	
Lime and Anhydrite	1,780'	1,800'	
Shale	1,800'	1,860'	
Shale and Shells	1,860'	2,100'	
Lime and Shale	2,100'	3,610'	
Lime	3,610'	3,725'	
Lime and Shale	3,725'	3,903'	
Conglomerate	3,903'	3,950'	
Lime	3,950'	3,975'	
		3,975'	Dry and abandoned.

Certificate

I, W. E. Cruce, of Barnett Drilling, Inc., hereby certify that to the best of my knowledge and belief, the above is a true and correct log of the Justus Well No. 1, located in the NE¹/₄ NE¹/₄ NE¹/₄ of Section 22-9S-22W, Graham County, Kansas.

W. E. Cruce

Subscribed and sworn to before me, in and for the County of Sedgwick, State of Kansas, this 25th day of July, 1951.

Delaine Olivier
Notary Public

My Commission Expires:

May 12, 1955

PLUGGING
FILE SEC-22T-9-R-24W
BOOK PAGE-97 LINE-9

7-30-51
RECEIVED
STATE COMMISSION
JUL 30 1951
CONSULTATION DIVISION
Wichita, Kansas