

15-065-00243-00-00

WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

FORMATION PLUGGING RECORD

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Strike out upper line when reporting plugging off formations.

Graham County. Sec. 25 Twp. 9S Rge. 22 (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NE NW NE

Lease Owner Lario Oil & Gas Co.

Lease Name Gustafson Well No. 1

Office Address 301 South Market, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 28, 19 51

Application for plugging filed August 28, 19 51

Application for plugging approved August 29, 19 51

Plugging commenced August 29, 19 51

Plugging completed August 29, 19 51

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation Arbuckle Depth to top Bottom Total Depth of Well 3967' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8 5/8", 184', None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Total Depth 3967'. Filled with heavy mud to bottom of 8 5/8" which was set at 184'. Set Halliburton plug at 180' with 15 sacks cement on top of plug. Filled with heavy mud to 35'. Set Halliburton plug with 10 sacks of cement for cap.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lario Oil & Gas Company Address 301 South Market, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick Leo L. Ross (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo L. Ross

301 South Market, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of September 19 51

My commission expires July 21, 1954

Notary Public



PLUGGING SEP 28 1951 CONSERVATION DIVISION FILE SEC-25 T-9-R 246 PAGE 106 LINE 17

9-28-51

15-065-00243-00-00

CERTIFIED DRILLERS LOG

Company: Lario Oil & Gas Company
Contractor: H & H Drilling Company
Commenced: 8-17-51
Completed: 8-29-51
Elevation: 2381 D.F.
Potential: DAA

Lease: Gustafson #1
Location: NE NW NE 25-9-22W
Graham Co., Kansas

Casing Record:
184' 8-5/8" cem. w/125 sax.

FORMATION	DEPTH	REMARKS
Clay	0-30	
Shale	30-184	
Shale & Shell	184-1040	
Gray shale, streak of sand	1040-1189	
Shale & Shell	1189-1890	
Anhydrite	1890-1918	
Shale & Shell	1918-2275	
Lime	2275-2305	
Lime & Shale	2305-2745	
Brown Lime	2745-2840	
Lime	2840-3085	
Shale & Lime	3085-3310	
Lime	3310-3851	
Lime & Shale	3851-3892	
Shale	3892-3920	
Conglomerate	3920-3935	
Arbuckle lime	3935-3950	
Lime	3950-3967	
Total Depth	3967	

I hereby certify that this is a true and correct copy of the above log, to the best of my knowledge.

[Handwritten Signature]

STATE OF KANSAS)
COUNTY OF SEDGWICK)

Subscribed and Sworn to before me this 31st day of August 1951.



Georgia L. Landi
Notary Public

9-28-51

My Commission Expires: May 13, 1953

INDEXING
FILE SEC 25 T 9 R 204
BOOK PAGE 106 LINE 27