
15-065-00764-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Graham County. Sec. 25 Twp. 9 Rge. 22 (E) (W)

Location as "NE/CNW¼SW¼" or footage from lines NW SE NE

Lease Owner Petroleum, Inc.

Lease Name GUSTAFSON Well No. 1

Office Address 311 East Third, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 1, 1955

Application for plugging filed January 1, 1955

Application for plugging approved January 1, 1955

Plugging commenced January 1, 1955

Plugging completed January 1, 1955

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3942 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	204'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 200' and placed first wooden plug at 200'. Placed 1/2 sack hulls on top of plug. Displaced 15 sacks cement through drill pipe on top of hulls. Mudded up to 40' and set second wooden plug and placed 1/2 sack hulls on top of plug. Filled hole to base of well cellar with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 27
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address R.R. #2 - Great Bend, Kansas

1-27-55

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Karl E. Becker (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker

311 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1955

Notary Public.

My commission expires 8-11-58

PLUGGING
FILE SEC 25 T 9 R 22W
BOOK PAGE 20 LINE 6

5-44M

WELL LOG

15-065-00764-00-00

COMPANY Petroleum, Inc.

SEC. 25 T. 9S R. 22W

FARM GUSTAFSON NO. 1

LOC. NW SE NE


TOTAL DEPTH 3942'

COUNTY Graham County, Kansas

COMM. December 19, 1954. COMP. January 1, 1955.

CONTRACTOR Garvey Drilling Company

CASING 8-5/8" @ 204' w/135 sax.



ELEVATION 2375' RB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

		Tops:	
150	Shale & Sand		
1867	Shale & Shells	Heebner:	3551 (-1176)
1905	Anhydrite	Toronto:	3576 (-1201)
2640	Shale & Shells	Lansing:	3591 (-1216)
3580	Lime & Shale	Arbuckle:	3929 (-1554).
3942	Lime		
3942	T.D.		

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1955
CONSERVATION DIVISION
Wichita, Kansas

1-27-55

State of KANSAS }
County of SEDGWICK } ss:

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the GUSTAFSON #1 well.

Karl E. Becker

Subscribed and sworn to before me this 17th day of January, 1955

My Commission Expires: 8-11-58

NOTARY PUBLIC

PLUGGING
FILE SEC 25 T 9 R 22W
BOOK PAGE 90 LINE 6

STATE OF KANSAS

15-065-00764-00-00

INVOICE

January 10, 1955 19

To: Petroleum, Inc.
305 E. 3rd
Wichita, Kansas

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

FOR: PLUGGING ASSESSMENT AS FOLLOWS:

Gustafson #1
NW SE NE 25-9-22W
Graham County
File No. 90-6 $25.00

NOTE: WE ALSO NEED A WELL PLUGGING APPLICATION, WELL LOG, & WELL PLUGGING RECORD ON THIS WELL TO COMPLETE OUR FILE.

Plt # 1363
1-27-55
Qtc -144

RETURN THIS COPY WITH REMITTANCE

24-7716-6-S 4-53-20M