

15-065-00770-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Graham SEC. 25 TWP. 9 RGE. 22 ~~NE~~ W
 Location as in quarters or footage from lines:
NE/NW/SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner John O. Farmer, Inc.
 Lease Name Gustafson "A" Well No. #1
 Office Address Box 352 - Russell, Kansas 67665
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced August 3, 1982
 Plugging completed August 13, 1982
 Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hamel
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3921'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	161'	NONE
				5 1/2"	3800'	837.14'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped sand to 3500' and five (5) sacks cement.
Shot pipe @ 3000', 2700', 2500', 2000', 1600', 1200', 1000' & 800'.
Pulled twenty-six (26) joints 5 1/2" casing.
Squeezed well with four (4) sacks hulls, ten (10) sacks gel, one (1)
sack hulls, seventy (70) sacks cement, ten (10) sacks gel -----
released plug and displaced seventy (70) sacks 50/50 pozmix cement
with 6% added gel and 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.

~~JAMES W. ROCKHOLD~~ (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1982



My Commission expires _____

Margaret Prosser
 STATE CORPORATION Notary Public.

AUG 23 1982
 8-23-82
 CONSERVATION DIVISION
 Wichita, Kansas