

15-065-02940-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Graham County. Sec. 25 Twp. 9S Rge. (E) 22 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Peel-Hardman

Lease Name Gustafson Well No. 1

Office Address P. O. Box 359, Hoisington, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oilwell

Date well completed 5-28 1950

Application for plugging filed 10-27 1954

Application for plugging approved 10-27 1954


Plugging commenced Nov. 23 1954

Plugging completed Nov. 5 1954

Reason for abandonment of well or producing formation No longer a commercial producer.

If a producing well is abandoned, date of last production 10-26 1954

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Lansing-Kansas City Depth to top 3760 Bottom _____ Total Depth of Well 3980 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	159'	8 5/8"	159'	None
		0	3760'	5 1/2"	3760'	1688'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3600'. Dumped 5 sacks of cement. Shot pipe off at 1688'. Pulled pipe and mudded hole to 150'. Dumped 15 sacks of cement at 150'. Finished mudding hole and dumped 10 sacks of cement at top of surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self

Address Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

William Herbert (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.


(Signature) William Herbert

(Address) _____

SUBSCRIBED AND SWORN to before me this 23 day of November, 1954

My commission expires June 4, 1955

Marian M. Herbert
Notary Public.



11-24-54

DRILLER'S LOG

15-065-02940-00-00

Company: Peel-Hardman

Sec. 25 Twp. 9S Rge. 22W
SW SW SW

Farm: Gustafson Well No. 1

Total Depth: 3985'

County: Graham, Kansas

Comm.: 5-3-50 Comp.: 5-11-50
Contractor: Glenn Peel Drilling Co., Inc.

Elevation:

Casing:
8 5/8" 159' cem.
5 1/2" 3760' cem.

Production: 132 bbls. per day

Figures below indicate bottom of formations

Surface and Clay Sand	0 -	40
Sand and Shale		120
Shale		750
Sand		850
Shale		975
Sand		1190
Sand Streak and Shale		1335
Sand		1585
Shale, Shells and Sand Streak		1852
Anhydrite		1897
Shale and Shells		2200
Lime and Shale		2445
Lime and Shale Streaks		2525
Lime		2725
Lime and Shale		3065
Lime		3495
Lime and Shale		3535
Lime		3985
Total Depth		3985

CABLE TOOL WORK

Bailing Mud 5-26-50
 Drilled plug, acidized w/1000 gals. 5-27-50
 and perforated
 Swab testing, acidized w/2000 gals. 5-28-50
 Swab testing, running tubing and rods 5-29-50
 Finish running rods and put on pump 5-30-50
 Swab test 3.5 bbls. per hr.

This is to certify that the above information is, to the best of our knowledge, true and correct.

GLENN PEEL DRILLING COMPANY, INC.

BY: Murdell K. Peel



SUBSCRIBED AND SWORN to before me this 11th day of October, 1950.

My commission expires June 4, 1951 M. M. Baker
Notary Public

16-28-54

PLUGGING
 FEB 35 25 9 22W
 BOOK PAGE 22 LINE 40