


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-065-21033-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County, Sec. 25 Twp. 9S Rge. 22W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NW NE NE  
Lease Owner TGT Petroleum Corporation  
Lease Name Gustafson #1 Well No.  
Office Address 209 E. William, Wichita, Ks 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 10/23/80 19  
Plugging completed 10/23/80 19  
Reason for abandonment of well or producing formation  
Depleted

If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation Depth to top Bottom Total Depth of Well 3910'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	None
				5-1/2"	3906.76'	3176'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from - feet to feet for each plug set.

Plugged with 3 sacks hulls, 70 sacks cement, 5 sacks gel, 8-5/8" plug, 60 sacks cement 50/50 pos 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 80

My commission expires



Joan Kelso  
RECEIVED Notary Public.  
STATE CORPORATION COMMISSION

OCT 29 1980  
629-80  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

15-065-21033-00-00

OPERATOR:	TGT Petroleum Corp.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Gustafson #1
LOCATION:	NW NE NE Section 25-9S-22W Graham County, Kansas
SPUD DATE:	August 8, 1978
COMPLETION DATE:	August 18, 1978

0	220	Surface sand & shale
220	1390	Shale & sand
1390	1624	Sand
1624	1882	Sand & shale
1882	1916	Anhydrite
1916	2270	Sand & shale
2270	2665	Shale
2665	3230	Shale & lime
3230	3523	Lime & shale
3523	3605	Lime
3605	3630	Lime & shale
3630	3770	Lime
3770	3800	Lime & shale
3800	3807	Lime
3807	3882	Lime & shale
3882	3910	Lime
	3910	Rotary Total Depth

Spud hole at 6:30 p.m., August 8, 1978. Drilled 222' of 12 1/4" hole. Ran 5 joints of 8-5/8" - 28# steel surface casing. Set at 219' with 175 sacks common cement, 3% CaCl, 2% gel. Cement did circulate. Job complete at 11:00 p.m., August 8, 1978.

T.D. 3910'. Ran 124 joints of 5 1/2" production casing. Set at 3907' G.L.

SAMPLE TOPS: Anhydrite 1882' (+ 480) B/Anhydrite 1916' (+ 446)

STATE OF KANSAS )  
 ) ss  
COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Gustafson #1, NW NE NE Section 25-9S-22W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
Jack L. Partridge,  
Assistant Secretary-Treasurer

10-6-80  
RECEIVED  
STATE CORPORATION COMMISSION  
OCT - 6 1980  
CONSERVATION DIVISION  
Wichita, Kansas

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 23rd day of August, 1978.

Sandra Richman  
Sandra Richman, Notary Public

NOTARY  
PUBLIC  
My commission expires July 21, 1979.

RECEIVED  
AUG 24 1978