


15-065-00371-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 28 Twp. 9 Rge. 22 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines. SW/4 SW/4 NE/4  
Lease Owner Davis Brothers & Transit Corporation  
Lease Name Moore Well No. 1  
Office Address 1516 Liberty Bank Bldg., Okla. City, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-7- 19 53  
Application for plugging filed 7-7- 19 53  
Application for plugging approved 7-7- 19 53  
Plugging commenced 7-7- 19 53  
Plugging completed 8-7- 19 53  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4079 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	198.81'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy drilling mud to 180', set plug and cemented with 15 sacks cement.  
Filled hole with heavy drilling mud to 40', set plug and cemented to bottom of cellar  
with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 17 1953  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Transit Corporation 7-17-53  
Address 1516 Liberty Bank Bldg., Okla. City, Okla.

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
C. W. Dodson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God!

(Signature) C. W. Dodson  
Oklahoma City, Okla.  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 53

My commission expires Feb. 14, 1957

Evelyn Culver  
Evelyn Culver Notary Public

PLUGGING  
FILE SEC 28 T 9 R 22  
BOOK PAGE 114 LINE 11

15-065-00371-00-00

DAVIS BROTHERS-TRANSIT CORPORATION ,et al.

MOORE #1  
SW SW NE Sec. 28-9S-22W  
Graham County

ELEVATION: DF 2381  
Gr 2379  
COMMENCED: June 22, 1953  
COMPLETED: July 7, 1953

FORMATION	FROM	TO
Surface	0	40
Sand	40	75
Sand & Shale	75	194
Shale & Shells	194	450
Sand & Shale	450	570
Shale & Shells	570	920
Shale & Shells	920	1180
Sand & Shale	1180	1900
Anhydrite	1900	1940
Shale	1940	2050
Lime & Shale	2050	2655
Lime Broken	2655	2755
Shale & Shells	2755	3157
Lime & Shale	3157	3205
Lime Shaled	3205	3469
Lime & Shale	3469	3660
Lime	3660	3718
Lime & Shale	3718	3815
Lime	3815	3846
Lime & Shale	3846	3898
Lime	3898	3996
Lime & Shale	3996	4050
Lime	4050	4070
		4079 T.D.

DRY HOLE

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

TRANSIT CORPORATION  
By: *E. W. Dodson*  
E. W. Dodson

Subscribed and sworn to before me this 15th day of July, 1953.

*Evelyn Culver*  
Evelyn Culver, Notary Public

My commission expires Feb. 14, 1957

**PLUGGING**  
FILE SEC 28 T 9 R 22W  
BOOK PAGE 114 LINE 11

7-17-53  
RECEIVED  
COMMISSION  
JUL 17 1953  
CORPORATION  
right-