

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-065-30307-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1965
8-27-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name C & G Drilling Company,
Complete Address: 107 Rule Building, Wichita, Kansas.
Lease Name Balthazor Well No. 1
Location NE-SE-SW Sec. 24 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 3450
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Above
Address: License No.
Operation Completed: Hour 5:00PM Day 23 Month 8 Year 1965

The Above well was plugged as follows:

180'--8 5/8" Surface pipe, cement circulated with 135 Sx.
Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.
cement thru DP. Heavy mud to 175', set plug with 1/2 sack hulls and dis-
placed 20 Sx. cement thru P. Heavy mud to 40', set plug with 1/3 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/27/65
INV. NO. 1905-W

Signed: W. L. Nichols
Well Plugging Supervisor