

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-01496-00-00

RECEIVED
STATE CORPORATION COMMISSION
1962
4-23-62
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham

Location: NW NW SE Sec. 25 Twp. 9 Rge. _____ (E) _____ (W) 21

Name of Field: _____ Total Depth: 3821

I have this date completed supervision of plugging of:

Lease Name: Teall Well No. B-1

Operator's Full Name: Morganstern-Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4:30 Day 17 Month 4 Year 62

The above well was plugged as follows:

8 5/8" 183' circulated with cement - 5 1/2" 3819' with 75 sax cement
Filled with sand to 3800', set 4 sax cement with dump bailer, pulled
1290' 5 1/2" to 525', circulated hole with heavy mud through 5 1/2" at 525'
Ø 30 sax Gel), displaced 20 sax cement through 5 1/2" at 525', heavy mud to
160', displaced 20 sax cement through 5 1/2" at 160', heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.
Mudding and cementing by Knight Company Pump Truck.

Signed: Edon Kelly
Conservation Division Agent

Reviewed: Harold Halls
Field Supervisor

Remarks:

INVOICED

DATE 5/7/62
INV. NO. 4895-w