

DISTRICT CONSERVATION AGENT'S REPORT

15-065-02440-00-00

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 133-29

LOCATION NW-SE-NW

SEC. 25 TWP. 9 RGE. 21-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease Fisher-A

Operator Bridgport Oil Co. Inc. Address #914 Central Bldg - Wichita

Field _____ County Sydney

Total Depth 3771 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 3/8 - 194 ft - Circulated with cement
5 1/2" casing set at 3767 ft cement with 200 sacks of
cement - Well Tested - No OH - Filled hole back
from bottom to 3750 ft - Put in 3 sacks cement at 3750
with Humphs Bailor - Shot off & recovered 1350 ft of
5 1/2" casing - Filled hole with mud to 200 ft - Plug &
15 sacks cement - Mud to 30 ft below the surface
& 10 sacks cement - filling hole to surface*

*Jim Barnes
Pipe Puller & Plugger*

C. M. Stough
District Conservation Agent

Date 11-10-47

12 1947
11-12-47

PLUGGING
FILE SEC 25 T 9 R 21W
BOOK PAGE 133 LINE 29