

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20182-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 14 1968  
CONSERVATION DIVISION  
Wichita, Kansas

11-14-68

Operator's Full Name Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas. 67202

Lease Name Van Loenen Well No. 1

Location NE-SW-NE Sec. 11 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3525

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Garvey Drilling Company,

Address: Route #2, Great Bend, Kansas. License No.     

Operation Completed: Hour 3:30 AM Day 9 Month 11 Year 1968

The Above well was plugged as follows:

2 1/4" -- 8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 100 Sx. cement thru  
DP from 1000' to 675'. Pull DP to 210' and displace 20 Sx. cement thru DP from 210' to  
150'. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols  
Well Plugging Supervisor

DATE 11/14/68

INV. NO. 8815-4