

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20209-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 3 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
3-369

Operator's Full Name George J. Ablah,

Complete Address: 8028 Cork, Wichita, Kansas.

Lease Name ~~VanLoenen~~ Van Loenen <sup>ILL ZAP</sup> Well No. 1

Location CNW-NE-SW Sec. 11 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3845'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: H-30, Incorporated,

Address: 200 North Main, Wichita, Kansas. License No.     

Operation Completed: Hour 2:30AM Day 1 Month 3 Year 1969

The Above well was plugged as follows:

208'-8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 100 Sx. cement thru  
DP from 950' to 625'. Pulled DP to 220' and displaced 20 Sx. cement thru DP from  
220' to 160'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols  
Well Plugging Supervisor

DATE 3/3/69  
INV. NO. 9402-u