

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1974

CONSERVATION DIVISION
Wichita, Kansas

10-9-74

15-065-20712-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name C & G Drilling Company & H. Rosen,

Complete Address 1107 Union National Bldg., Wichita, Kansas.

Lease Name Van Loenen Well No. 1

Location CN/2-NW-NW Sec. 11 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 8:00 AM Day 21 Month 9 Year 1974

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 110 Cu. Ft. cement
thru DP from 875' to 550'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/9/74

INV. NO. 72-w