

DISTRICT CONSERVATION AGENT'S REPORT

15-065-00264-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 58-41

LOCATION SE SE SW

SEC. 12 TWP. 9S RGE. 22W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Vesper

Operator Barnett Drilling, Inc. et al address 417 First National Bank Bldg.,
Wichita, Kansas

Field _____ County Graham

Total Depth 3896 Feet.

(Describe briefly the manner in which the well was plugged)

Filled hole with heavy mud from 3896 feet to 162 feet. Set
wooden plug at 162 feet. Filled surface casing with 1 sack
of hulls and 15 sacks of cement to 115 feet. Filled surface
casing with heavy mud from 115 feet to 35 feet. Set wooden plug
at 35 feet and filled surface casing with 1/2 sack of hulls and
10 sacks of cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 3 1951

CONSERVATION DIVISION
Wichita, Kansas

2-3-51

PLUGGING
FILE SEC 12 T 9 R 22W
BOOK PAGE 58 LINE 41

C. D. Stough
District Conservation Agent

Date January 10, 1951