

KANSAS  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

MAR 6 1962

CONSERVATION DIVISION  
Wichita, Kansas

3-6-62

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-065-02987-00-00

File No. \_\_\_\_\_ County: Graham

Location: NW NE NE Sec. 12 Twp. 9 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 22

Name of Field: \_\_\_\_\_ Total Depth: 3864

I have this date completed supervision of plugging of:

Lease Name: Hedge Well No. 2

Operator's Full Name: North American Oil Corp

Complete Address: Box 136 Paxton, Neb.

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11AM Day 2 Month 3 Year 62

The above well was plugged as follows:

~~8 5/8" 235' circulated with cement - 5 1/2" 3859' with 125 sax cement PB 36271  
perf 3470 - Filled with sand to 3450', set 4 sax cement with dump bailer, pulled  
2800' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" ( 24 Sax Gel),  
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced  
20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and filled to  
bottom cellar with cement.~~

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]

Conservation Division Agent

Reviewed: Harold Morris  
Field Supervisor

Remarks:

INVOICED

DATE 3/16/62

INV. NO. 4644-W