

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 25 1972  
CONSERVATION DIVISION  
Wichita, Kansas

2-25-72

15-065-20525-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name H. B. Mabée Company,

Complete Address P. O. Box #94718, Oklahoma City, Oklahoma.

Lease Name Justus Well No. 1

Location NE-SW-SW Sec. 15 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 4040'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 8:00 AM Day 2 Month 2 Year 1972

The above well was plugged as follows:

225'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 110 Cu. Ft. cement  
thru DP from 1050' to 725'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. G. Nichols  
Well Plugging Supervisor

DATE 2/28/72  
INV. NO. 5210-W