

15-065-21369-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County, Sec. 3 Twp. 9S Rge. 22W E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
SW SE SE


Lease Owner American Energies  
Lease Name Van Loenen Well No. 1  
Office Address 575 Fourth Financial Center, Wichita, KS.  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry hole

Date Well completed 3-4 1981  
Application for plugging filed 3-4 1981  
Application for plugging approved 3-4 1981  
Plugging commenced 3-4 1981  
Plugging completed 3-4 19

Reason for abandonment of well or producing formation  
dry hole  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3878  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	229'	8 5/8"	229	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

1st Plug set at 950' with 70 sacks cement 50-50 poz 6% gel

2nd Plug set at 200' with 20 sacks cement 50-50 poz 6% gel

3rd Plug set at 40' with 10 sacks cement 50-50 poz 6% gel

5 sacks cement in rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing

STATE OF Kansas COUNTY OF Graham, ss.  
Jerry M. Helberg (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on-oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.


(Signature)

*Jerry M. Helberg*  
Box 32, Morland, Kansas 67650  
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of March, 1981

*Janice Rehman*  
Notary Public.

My commission expires 12-4-83



RECEIVED  
STATE CORPORATION COMMISSION  
MAR 18 1981  
CONSERVATION DIVISION  
Wichita, Kansas

15-065-21369-00-00

DRILLERS LOG  
VAN LOENEN #1

CASING RECORD: OPERATOR: American Energies  
8 5/8" set at 229' CONTRACTOR: Helberg Oil  
TOTAL DEPTH: COMMENCED: February 21, 1981  
3878' COMPLETED: March 4, 1981

DESCRIPTION:  
SW SE SE  
Sec. 3-9-22 Graham County, Kansas

FORMATION	FROM	TO	REMARKS
Lime & Shale	0	40	
Lime & Shale	40	105	
Shale & Sand	105	239	
Shale & Sand	239	555	
Sand & Shale	555	1164	
Shale & Sand	1164	1676	
Shale & Sand	1676	1754	
Anhydrite	1754	1786	
Shale & Sand	1786	1896	
Shale	1896	2074	
Shale	2074	2227	
Shale	2227	2393	
Shale	2393	2540	
Shale & Sand	2540	2699	
Shale	2699	2826	
Shale	2826	2889	
Shale	2889	3016	
Shale	3016	3127	
Lime & Shale	3127	3250	
Lime & Shale	3250	3387	
Shale & Lime	3387	3464	
Lime & Shale	3464	3500	
Lime & Shale	3500	3511	
Lime & Shale	3511	3525	
Lime & Shale	3525	3572	
Lime & Shale	3572	3635	
Lime & Shale	3635	3697	
Lime & Shale	3697	3756	
Lime	3756	3768	
Lime	3768	3792	
Lime	3792	3860	
Lime	3860	3878	
T.D.	3878		D & A

I certify that the above is a true and correct copy of the log to the best of my knowledge.

HELBERG OIL COMPANY  
*Jerry M. Helberg*  
Jerry M. Helberg

Subscribed and sworn to before me this 17 day of March, 1981.

*Janice Robinson*  
Notary Public STATE OF KANSAS COMMISSION

My commission expires 12-4-83.

MAR 18 1981

CONSERVATION DIVISION  
Wichita, Kansas  
3-18-81

