


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 6 Twp. 9S Rge. 22W 1/4 NW
Location as "NE/CNW/SW" or footage from lines
SW/4 SW/4 SE/4

Lease Owner Graham-Michaelis Corporation
Lease Name Gustafson Well No. I-6
Office Address P. O. Box 247, Wichita, Kansas 67201
Character of Well (Completed as Oil, Gas or Dry Hole) D & A



Locate well correctly on above
Section Plat

Date Well completed August 27, 1980
Application for plugging filed August 27, 1980
Application for plugging approved August 27, 1980
Plugging commenced August 27, 1980
Plugging completed August 27, 1980
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,030
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	273.03'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole @ 950' w/70 sx cement
@ 260' w/20 sx cement
@ 40' w/10 sx cement
5 sx cement in rathole

RECEIVED
STATE CORPORATION COMMISSION

SEP - 9 1980

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Red Tiger Drilling Company
1720 KSB&T Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss. contractor
Gloria Fawcett (employee of ~~owner or operator~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 KSB&T Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 19 80.



Jimmie L. Farrige
Notary Public.

My commission expires _____

15-065-21292-00-00

DRILLERS LOG

No. 1-6 Gustafson

CASING RECORD:

COMPANY:

Graham-Michaelis Corporation

DESCRIPTION:

8 5/8" @ 281'
w/180 sx cement

CONTRACTOR:

Red Tiger Drilling Company

SW/4 SW/4 SE/4
Sec. 6-T9S-R22W

COMMENCED:

August 18, 1980

Graham County, Kansas

D & A

COMPLETED:

August 27, 1980

TOTAL DEPTH: 4,030'

ELEVATION: 2,325' KB

FORMATION

FROM

TO

REMARKS

Surface Soil

0

285

Shale & Sand

285

1230

Sand

1230

1290

Shale

1290

1405

Sand

1405

1655

Shale & Red Bed

1655

1913

Anhydrite

1913

1945

Shale

1945

2555

Lime & Shale

2555

2880

Shale & Lime

2880

3089

Lime & Shale

3089

3255

Lime

3255

4030

RTD

4030


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 3rd day of September, 1980.

Jimmie L. Farrice
Notary Public



RECEIVED
STATE CORPORATION COMMISSION
SEP - 9 1980
CONSERVATION DIVISION
Wichita, Kansas
9-9-80