

B & H Drilling, Inc.
Ninemire #1

Sec. 7, Twp. 9, Rge. 22
County: Graham, Kansas

Total Depth: 4120'
Comm: 6/5/48 Comp: 6/17/48

Top Arbuckle 4087'
Top Lansing-K.C. 3682'

Casing
8 5/8" Set @ 173'

Cement
125 Sx - Circulated

Formation	Depth
Surface Soil	20
Sand	28
Shale & Shells	60
Sand	72
Shale & Shells & Sand	173
Shale & Shells	1070
Sand & Shale	1245
Shale & Shells of Pyrite	1275
Sand	1290
Shale & Shells	1400
Red Bed, Sand & Shale	1520
Sandy Red Rock	1750
Red Rock, Shale & Shells	1995
Anhydrite	2035
Shale, Shells & Red Rock	2170
Shale & Shells	2440
Shale & Lime	2650
Lime	2690
Shale & Lime	3682
Lime	3940
Lime & Shale	4087
Lime Arbuckle	4120

STATE OF KANSAS)
RUSSELL COUNTY) SS

I hereby certify that the above information is true and correct to the best of my knowledge.

6-25-48

Jane Duncan

JUN 25 1948

Subscribed and sworn to before me this 23rd day of June, 1948.

Clara Hummel

Notary Public



My Comm. Expires 6/17/50

