


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 8 Twp. 9S Rge. (E) 22 (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW%SW%" or footage from lines _____
Lease Owner Chief Drilling Co., Inc.
Lease Name Gaylord Well No. 1
Office Address Box 97 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2/12 1958
Application for plugging filed 2/12 1958
Application for plugging approved 2/12 1958
Plugging commenced 2/12 1958
Plugging completed 2/12 1958
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A.D. Fabricius - Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3890 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1/2 sack of hulls and wooden plug set @ 500', mixed 25 sacks cement through drill pipe; 1/2 sack of hulls and wooden plug set @ 220', mixed 15 sacks of cement through drill pipe; plug set @ 40' with 10 sacks cement.

STATE CORPORATION COMMISSION

FEB 14 1958

CONSERVATION DIVISION

2-14-58

Name of Plugging Contractor Chief Drilling Co., Inc. (If additional description is necessary, use BACK of this sheet)
Address Box 97 - Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover
Box 97 - Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 1958

My commission expires Jan. 26, 1959.
Carmen Reinhardt Leiker Notary Public.



PLUGGING
FILE SEC 8 T 9 R 22
BOOK PAGE 82 LINE 24

13-065-00932-00-00

WELL LOG

No. 1 Gaylord

Elevation: 2372 DF
2369 GR
2375 KB

Chief Drilling Co., Inc.
Box 97
Great Bend, Kansas

Commenced: 2/4/58
Completed: 2/12/58

No. 1 Gaylord
NW NW SW Sec. 8-9S-22W
Graham County, Kansas

Plugged & Abandoned

Contractor: Chief Drilling Co., Inc.
Rotary: 0 - 3890' T.D.

Casing Record: Set 230' of 8 5/8" Used 32# casing w/175 sacks Pozmix.
Cement circulated.

Figures Indicate Bottoms of Formations

Formation Tops & Minus

Surface Clay & Sand	0 - 230
Shale	230 - 820
Shale & Sand	820 - 1080
Shale & Shells	1080 - 1430
Sand & Shale	1430 - 1450
Shale	1450 - 1525
Sand	1525 - 1680
Shale	1680 - 1948
Anhydrite	1948 - 1980
Shale & Shells	1980 - 1995
Shale & Lime	1995 - 3630
Lime	3630 - 3890 T.D.

Anhydrite	1948 / 427
Heebner	3626 - 1251
Lansing	3659 - 1284

State of Kansas)
County of Barton)


I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the NW NW SW of Sec. 8-9S-22W, Graham County, -Kansas to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed to and sworn to before me this 13th day of February 1958.

Carmen Reinhardt Leiker
Carmen Reinhardt Leiker,
Notary Public



STATE COMMISSION
2-14-58
FEB 14 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 8 T 9 R 22
BOOK PAGE 82 LINE 24