

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

*RCV
5/26/98*

API NUMBER 15-065-20312 - 0050

LEASEE NAME Casey Jones

WELL NUMBER 1-1

42906 15t. from S Section Line
1:29

1650 Ft. from E Section Line

SEC. 1 TWP. 9S RGE. 23 (W) or (W)

COUNTY Graham

Date Well Completed 5/11/70

Plugging Commenced 4/22/98

Plugging Completed 4/22/98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Eagle River Energy Corporation

ADDRESS 7060 S. Yale, Suite 609, Tulsa, OK 74136

PHONE# (918) 494-8928 OPERATORS LICENSE NO. 31070

Character of Well oil producer

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/04/98 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation Lansing-Ks City Depth to Top 3590 Bottom 3750 T.D. 3790'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Topeka	lime-oil/water	3302	3527	8 5/8	195'	none
Heebner	shale	3527	3549	5 1/2	3789'	none
Toronto	lime-oil/water	3549	3561			
Lansing	lime-oil/water	3561	3785			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from _____ feet to _____ feet each section.

Backhoe dig out cellar to bradenhead. L-K wireline perf w/3 shots in Dakota at 1150 and Anhydrite at 1930. RU Allied Cementing, went down 5 1/2 csg, mix and pump 25 sx cement w/200# hulls follow w/12 sx gel, follow w/175 sx cement w/200# hulls 1000# max psi. Shut-in psi 500#. Down 8 5/8 csg mix & pump 25 sx cement 100# hulls, max

(If additional description is necessary, use BACK-of-this-form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Eagle River Energy Corporation

STATE OF OK COUNTY OF Tulsa, ss.

Mark P. Godsey (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed is the same as true and correct, so help me God.

(Signature) Mark P. Godsey

(Address) Same as above

SUBSCRIBED AND SWORN TO before me this 13th day of May, 1998

Dora R. Biavette
Notary Public

My Commission Expires: 8-7-2000

