


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Graham County, Sec. 3 Twp. 9S Rge. 23W (E) (W)  
Location as "NE/CNW&SWX" or footage from lines S/2 SW SW  
Lease Owner Nadel and Gussman  
Lease Name QUINT Well No. 1-A  
Office Address 32nd Floor, First National Tower, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 1 19 75  
Application for plugging filed August 31, 19 75  
Application for plugging approved August 31 19 75  
Plugging commenced September 1 19 75  
Plugging completed September 1 19 75  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3850 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom plug at 950' w/70 sacks 50/50 Pozmix, 6% Gel.

Middle plug at 200' w/25 sacks 50/50 Pozmix, 6% Gel.

Top plug at 40' w/1/2 sack hulls and 10 sacks 50/50 Pozmix, 6% Gel.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 03 1975

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Duke Drilling Co.  
Address Box 823, Great Bend, Kansas 67530  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS COUNTY OF BARTON  
Wayne Dobbs (employee of owner) or (owner) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.


(Signature) Wayne Dobbs

Box 823, Great Bend, Kansas 67530

(Address)

Subscribed and sworn to before me this 2nd day of September, 19 75

April 11, 1978



Dorothy M. Hague  
Notary Public.

18-065-20775-00-00

DRILLERS' WELL LOG

DATE COMMENCED: August 25, 1975  
DATE COMPLETED: September 1, 1975

Nadel and Gussman  
QUINT 1-A  
S/2 SW SW of Sec 3-T9S-R23W  
Graham County, Kansas

ELEVATION: 2287 K.B.

0 - 70' Clay  
70 - 640' Shale and Clay  
640 - 1939' Shale, Sand Streaks  
1939 - 1975' Anhydrite  
1975 - 3358' Shale and Lime  
3358 - 3579' Lime  
3579 - 3583' Shale  
3583 - 3850' Lime and Shale

FORMATION TOPS  
Anhydrite 1939  
Topeka 3358  
Heebner 3579  
Toronto 3600  
Lansing 3616  
RTD 3850

SURFACE PIPE:  
Set used 28#, 8 5/8" @ 183'  
w/140 sacks common, 2% Gel,  
3% cc.

A F F I D A V I T

STATE OF KANSAS }  
COUNTY OF BARTON } ss.

Wayne Dobbs, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 2nd day of September, 1975.

Dorothy M. Hague  
Notary Public

My Commission Expires: April 11, 1978

RECEIVED  
STATE CORPORATION COMMISSION

SEP 03 1975

9-3-75

CONSERVATION DIVISION  
Wichita, Kansas