



15-065-20364-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas

9-20-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Delbert Adams of Forbes Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Adams guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: P. O. Box #352, Russell, Kansas.

Lease Name: Harvey Well No. 1

Location: SE-SW-NW Sec. 19 Twp. 9 Rge. (E)(W) 23

County: Graham ORIGINAL TD 3995'  
Total Depth 3955' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Adams was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3994'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3935'. Top perforations from 3921' to 3926'.

Sand well back to 3900' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement, staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent