

State of Kansas



15-065-30187-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1966

60-29-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Empire Drilling Company has this

date requested permission to plug the following described well:

Martin Oil Co.,

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Martin Oil Company,

Complete Address: 527 Union Center Bldg., Wichita, Kansas.

Lease Name: Scriven Well No. 1

Location: NW-NW-SE Sec. 19 Twp. 9 Rge. (E)(W) 23

County Graham Total Depth 4010 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

153'--8 5/8" Surface pipe, cement circulated with 75 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	150' with $\frac{1}{4}$ sk. hulls &
		20 Sx. cement.
"	"	40' with $\frac{1}{2}$ sk. hulls &
		10 Sx. cement.

Very truly yours,

Conservation Division Agent