



15-065-21677-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Rich Pfaff of Raine & Williamson ^(Pige) has this date requested permission to plug the following described well:

Operator's Full Name: Raine & Williamson Oil Co. Inc. 67202

Complete Address: 435 Page Court - 220 West Douglas, Wichita Mo.

Lease Name: Gano Well No. #3

Location: NW-SE-NE Sec. 30 Twp. 9^S Rge. 23^W (E) (W)

County: Graham Total Depth: 4080 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Pfaff was instructed to plug the well as follows: By

8 5/8" - 282^{FT} sp. cur. w/ 200ST Comm. - 2% Gel - 3% Ca-Cl. (Sun)

Order 140ST 50/50 Foam 4% Gel - 3% Ca-Cl. 9 8 5/8" Plug.

Spot with Drill Stem - with heavy mud between all plugs.

1ST Plug. @ 1200 FT w/ 80ST Cont.

2ND Plug. @ 300 FT w/ 40ST Cont.

3RD Plug. -> solid bridge @ 40^{FT} to 0 w/ 10ST Cont.

10ST In Bat Hole (circulate) (By Sun Cont)

Very truly yours,

Maurice Schmidt
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1982

CONSERVATION DIVISION
Wichita, Kansas

8-23-82