



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1972
08-08-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20557-00-00

Dear Sir:

Mr. Johnnie Crowe of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company,

Complete Address: 217 North Water, Wichita, Kansas.

Lease Name: Orval Keith Well No. 1-V

Location: SE-SW-NW Sec. 2 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4000' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

2 1/4'--10 3/4" Surface casing, cement circulated with 150 Sx. (8 3/4" Hole).
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 140 Cu. Ft. cement thru DP. Pull DP to 245' and displace 45 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 15 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent