



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED
JAN 29 1973
01-29-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20580-00-00

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company,

Complete Address: 217 North Water, Wichita, Kansas.

Lease Name: Wilma M. Harvey Well No. 1-V

Location: SW-NE-SE Sec. 2 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4040' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fickel was instructed to plug the well as follows:

220'--10 3/4" Surface casing, cement circulated with 200 Sx. (9" Hole).
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 165 Cu. Ft. cement thru DP. Pull DP to 245' and displace 40 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1 sack hulls and 20 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent