



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 13 1963
 11-13-1963
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bob White of Empire Drilling Co., has this date requested permission to plug the following described well:

Mr. White guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kans.

Lease Name: Ida Keith Well No. # 2

Location: NE-SW-SW Sec. 3 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3926 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. White was instructed to plug the well as follows:

150'--8 5/8" Surface pipe, cement circulated . 3921'--5 1/2"
Production casing cemented with 75 Sx. Top perforations
3903' to 3909'

Sand well back to 3890' and set 5 Sx cement with dump bailer.
Pull 5 1/2" to 600', circulate heavy gel mud, pull 5 1/2" to 540'
and displace 20 Sx. cement thru casing. Pull 5 1/2" to 150' and
displace 20 Sx. cement thru casing. Pull 5 1/2", set rock bridge
@ 30' and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. D. Dehls
 Conservation Division Agent