



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-20311-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1970
CONSERVATION DIVISION
Wichita, Kansas
03-27-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated.

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Minium Well No. 1

Location: 440'-NSL & 440' EWL Sec. 7 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4062' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

309'--7" PD Surface casing, cement circulated with 100 Sx.
Top of Dakota section @ 1300'

Circulate hole with heavy mud. Pull DP to 1500' and displace 60 Sx.
cement. Pull DP to 300' and displace 20 Sx. cement. Pull DP, set
bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. G. Nichols
Conservation Division Agent