

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20908-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1971
CONSERVATION DIVISION
Wichita, Kansas

12-20-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB & T Building, Wichita, Kansas.

Lease Name Willis Well No. 1

Location App: CNE-SE Sec. 18 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3895'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 8:30 PM Day 16 Month 12 Year 1971

The above well was plugged as follows:

299'--8 5/8" Surface casing, cement circulated with 230 Sx.
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 110 Cu. Ft. cement
thru DP from 1075' to 750'. Pulled DP to 310' and displaced 30 Cu. Ft. Cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 1-6-72
INV. NO. 4854-W