

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-065-30003-00-00

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1965

1-5-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leben Drilling, Incorporated,

Complete Address: Box #486, Great Bend, Kansas.

Lease Name Sullivan Well No. 1

Location CSW-SW Sec. 19 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3910

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 4:45AM Day 2 Month 1 Year 1965

The Above well was plugged as follows:

213'--8 5/8" Surface pipe, cement circulated with 165 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

TE 1-5-65

NO. 472.W

Signed: K. A. Nichols
Well Plugging Supervisor