

R

DISTRICT CONSERVATION AGENT'S REPORT

15-065-00292-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 66-8
LOCATION SW SW SE
SEC. 25 TWP. 9 RGE 22

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. B-1 Lease Gustafson B^{KCC} ZAP
Operator Peel-Hardman Address Box 359 Hoisington, Kans
Field _____ County Graham
Total Depth 4050 Feet.

(Describe briefly the manner in which the well was plugged)
8 5/8" 189' - 5 1/2" 3843' with 125 sax cement behind - Lane Well s
plugs to 3680' - top perforations at 3612'.
Filled with sand to 3600', set 4 sax cement with dump bailer,
pulled approx 1100' 5 1/2" - filled with mud to 189', set rock
and 15 sax cement - mud to 35', set rock and 10 sax cement to
bottom cellar.

Edson Terry
District Conservation Agent
Date 4-30-53

RECEIVED
STATE CORPORATION COMMISSION
MAY - 5 1953
CONSERVATION DIVISION
Wichita, Kansas
55-53

PLUGGING
FILE SEC 25 T 9 R 22
BOOK PAGE 44 LINE 8