

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-065-00770-00-00 *P*

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name John O. Farmer

Complete Address Russell, Kansas

Lease Name Justafson A ^{KCC} ZAP Well No. A-1

Location NE-NW-5W Sec. 25 Twp. 9 Rge. 22 (East) (~~West~~)

County Stalam Total Depth 3921'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineers (Deacon Pulley)

Address W. Bend, Kansas License No. _____

Operation Completed: Hour: 12:15pm Day: 13 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" @ 161' w/100 sx - 5 1/2" @ 3800' w/125 sx
Plug back T.D. 3600' - Top Refs @ 3574' - Sand
to 3500' & dump 5 sx cont. - Recovered 800 lbs 5 1/2" casing
Ordered 140 sx 5/8" prog - 60 gal - 3% cc & 8 5/8" plug,
20 gal, & 5 hulls: Pumped in 4 hulls -> 10 gal ->
1 hull -> 70 cont -> 10 gal -> Rel plug -> 70 cont.
Max PSI 750# - Shut-in 12:15pm w/600# PSI

Amount of Surface Casing: 161'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis J. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION
RECEIVED
OCT 15 1982
CONSERVATION DIVISION
Wichita, Kansas

Conservation Division Agent

INVOICED

DATE 10-25-82

INV. NO. 1429-W

10-15-82