

KANSAS

*2*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
7-17-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20349-00-00

Operator's Full Name Martin Exploration & Petroleum Inc.

Complete Address 527 Union Center

Lease Name Allen Well No. 1

Location SE SW SW Sec. 28 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3905

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Aspen Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 12:30A Day 15 Month 7 Year 1970

The above well was plugged as follows:

RTD 3905' 8 5/8 csg set at 209' cwc Cmt. Mat. 100 sk 50-50 poz W/6% gel.

Gunned pits, circulated heavy y mud, set cementing plug at 900' and displaced 70 sk

cmt thru drill-pipe. Heavy mud-to-210' set cementing plug and displaced 20-sk cmt.

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *L. A. Massey*  
Well Plugging Supervisor

INVOICED  
DATE 7/17/70  
INV. NO. 2239-W