

15-065-20511-00-00

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1972
CONSERVATION DIVISION
Wichita, Kansas

1-26-72

Operator's Full Name Dreiling Oil, Incorporated.

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Cook Well No. 1

Location CNW-NW Sec. 28 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3642'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 5:00 AM Day 25 Month 1 Year 1972

The above well was plugged as follows:

191'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 110 Cu. Ft. cement
thru DP from 1025' to 700'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 1-28-72
INV. NO. 5067-11