

**KANSAS**  
**STATE CORPORATION COMMISSION**

CONSERVATION DIVISION AGENT'S REPORT

15-065-03016-00-00

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 25 1962

CONSERVATION DIVISION  
Wichita, Kansas

9-25-62

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Thunderbird Drg Co

Complete Address: 712 Union Center Wichita, Kansas

Lease Name Sharpe Well No. 1

Location NW SW NW Sec. 33 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3874

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Operation Completed: Hour 3PM Day 20 Month 9 Year 62

The Above well was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/2" ~~3818'~~ 3874' - perforated 3818'

Sand back to 3750', set 4 sax cement with dump bailer - pulled 1035' 5 1/2"  
to 550' - pumped gel mud in hole - tried to circulated - hole pressured up -  
pulled 5 1/2" to 450', circulated hole with heavy gel mud ( 20 sax), displaced  
20 sax cement through 5 1/2" at 450', heavy mud to 180', displaced 20 sax  
cement through 5 1/2" at 180', heavy mud to 30', filled with cement 30' to 0'

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 9/29/62

INV. NO. 5456-u

Signed: Edson Petty  
Well Plugging Supervisor