

8

DISTRICT CONSERVATION AGENT'S REPORT
15-065-00326-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 150-13
LOCATION NE NE SW
SEC. 34 TWP. 9 RGE. 22

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. KCC 211 / Lease Sandlin

Operator Compass Oil & Uranium Address c/o West Supply Co Chase, Kan

Field _____ County Graham

Total Depth 3809 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____
(Describe briefly the manner in which the well was plugged)

8 5/8" at 278' circulated with cement - 4 1/2" at ?
Filled with sand to 3500', set 4 sax cement with dump bailer,
pulled 2100' 4 1/2" - mud to 275', set rock and 15 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1955

CONSERVATION DIVISION
Wichita, Kansas

Eldon Felty
District Conservation Agent
Date 9-13-55

920-55

PLUGGING
FILE SEC 34 TWP 9 R 22W
BOOK PAGE 150 LINE 13