

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-065-20060-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1967

7-18-67

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name H. C. Bennett,

Complete Address: 1212 Union National Bank Bldg., Wichita, Kansas.

Lease Name McElroy Well No. 1

Location CS/2-NE-SE Sec. 34 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3845

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sage Drilling Company, Incorporated,

Address: 500 Bitting Building, Wichita, Kans. License No.

Operation Completed: Hour 5:30 PM Day 9 Month 7 Year 1967

The Above well was plugged as follows:

241'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, Displaced 80 Sx. cement thru DP. from

1590' to 1290'. Pulled DP. to 240' and displaced 20 Sx. cement thru DP.

Pulled DP. Set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Fickel
Well Plugging Supervisor

DATE 7/18/67

INV. NO. 5989-4