

KANSAS

*2* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20523-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 3 1972  
CONSERVATION DIVISION  
Wichita, Kansas

2-3-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Building, Wichita, Kansas

Lease Name Sandlin Well No. 1

Location SW-SW-NW Sec. 34 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3835'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 2:30 AM Day 31 Month 1 Year 1972

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud, pulled DP to 975' and displaced 110 Cu. Ft. cement thru  
DP from 975' to 650'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru DP from  
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Nichols*  
Well Plugging Supervisor

DATE 2/3/72  
INV. NO. 5118-W