

KANSAS

**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION  
DEC 21 1967  
12/21/67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt.  
Complete Address Drawer #370, Hays, Kansas.  
Lease Name Loyd Well No. 4  
Location SW-NW-NW Sec. 26 Twp. 9 Rge. (E) (W) 24  
County Graham Total Depth 4030'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor L. J. Dreiling & Sons, Incorporated.  
Address Victoria, Kansas. License No.       
Operation Completed: Hour 11:20AM Day 19 Month 12 Year 1967

The above well was plugged as follows:

212'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
Dakota section from 750' to 940'.  
Circulated hole with heavy mud. Pulled DP to 960' and displaced 100 Sx. cement thru  
DP from 960' to 640'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from 215'  
to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: A. L. Nichols  
Well Plugging Supervisor

DATE 12/22/67  
INV. NO. 6960-44