

6 070313

API NUMBER 15-163-22, 699-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE-SW-NE, SEC. 14, T. 9 S, R. 20 W

2970 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9476

Lease Name Lambert Well # 1

Operator: G.O. oil operations

County Roofs 119.83

Name & Address P.O. Box 441

Well Total Depth 2687 feet

Hays, Kans. 67601

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8" feet 219

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated 146 #1617

Plugging Contractor R & C Drilg. Inc License Number 9087

Address Hays, Kans. 67601

Company to plug at: Hour: 4:00 PM Day: 23 RD Month: JUNE Year: 19 85

Plugging proposal received from John Weis

(company name) R & C Drilg Inc (phone) 913-628-2560

were 8 5/8" 219 ET SP. CUC 1/150 SK Common quick set (By allied cont)

order 220 SK 50/50 Pozmix 50/50 Pozmix 6% Gel - 1 SK Cello and 8 5/8" Plug

spot with Drill Stem (Recondition cable (45 Vis) Heavy Mud Between All Plugs

no Circulation Problems, Mud Condition weight 9.9. Vis. 42,

Tabackle Well @ 2665 ET, ELV. 2139, Anh. 1601

Plugging Proposal Received by Marion Schmidt
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour 4:00 PM Day: 23 RD Month: JUNE Year: 19 85

ACTUAL PLUGGING REPORT Ordered 220 SK 50/50 Pozmix 6% Gel - 1 SK Cello

spotted with Drill Stem Reconditioned Well, Heavy Mud Between All Plugs

1st Plug @ 2665 ET 1/25 SK cont, 2nd Plug @ 1620 ET 1/25 SK cont,

3rd Plug @ 920 ET 1/100 SK cont 1/2 SK Cello, 4th plug @ 240 ET 1/50 SK cont,

5th Plug Solid Bridge @ 40 ET to 0 1/10 SK cont, 10 SK In Part (circ)

(Cemented by Allied Cont)

Remarks: (If additional description is necessary, use BACK of this report)

STATE CORPORATION COMMISSION
07-01-1985
JUL 01 1985

INVOICED

DATE 7-10-85

INV. NO. 8806

Signed Marion Schmidt
DOIC (TECHNICIAN) 6-28-85