

6 030697

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163 22838-00-00

1/2 NW 1/4 SEC. 14, T 9 S, R 20 W

4290 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Lease Name ROBERTSON Well # 1

Operator: MID-CONTINENT ENERGY CORP. County ROOKS 119.34

Name & Address 120 S. MARKET ST. 300

Well Total Depth 3672 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 217'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: AM Day: 20 Month: 3 Year: 19 86

Plugging proposal received from TOM

(company name) KELSO CASING (phone) _____

were: 8 5/8 @ 217' w/ 150 SX 4 1/2 @ 3670 w/ 125 SX. PERF 3632-40'

PBTD 3670' ORDER SAND & COM. CMT. SHOOT & STRIP PIPE

ORDER 180 SX. 60/40 POZ. 6" GEL 3 1/2" 40 SX. GEL 4 SX. HULLS.

ALLIED CMT CO. OWS WATER TRUCK.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: _____ Day: 20 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 3580' SPOT 4 SX. COM. CMT.

ON SAND w/ BAILER SHOT & STRIPPED 2814' OF 4 1/2"

HOOK ON TO 8 5/8 MIX. & PUMP 3 SX. HULLS 32 SX. GEL 100 SX. CMT MIX + 1 SX.

HULLS 8 SX. GEL 80 SX. CMT. MIX. MAX. PSI 600 * CLOSE IN 250 *

PLUG COMPLETE

RECEIVED
STATE CORPORATION COMMISSION
04-07-1986
APR 7 1986

Remarks: _____

(If additional description is necessary, use BACK of this CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE APR 8 1986

Signed Carl Goodrow
(TECHNICIAN)

REV. NO. 13334