

9-11

4-070059

TO:

API Number: 15-163-21,704-00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

C SE \_\_\_\_\_ /4 SEC. 17, 09 S, 20 W  
1320 \_\_\_\_\_ feet from S section line  
1320 \_\_\_\_\_ feet from E section line

Operator license# 6139

Lease: Simoneau "B" Well # 1

Operator: Jay C. Boyer

County: Rooks 125.87

Address: P.O. Box 511  
Hays, Kansas 67601

Well total depth 3873 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 265 feet  
W/175 sxs.

ABAND. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD. \_\_\_\_\_, D&A \_\_\_\_\_

Plugging contractor: Kelso Casing Pulling, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 10:00 A.M. Day: 11 Month: September Year: 1997

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pulling, Inc. Phone: 316-938-2634

Were: Perfs at 3794' - 3824'. Dakota 739' - 1039'. Anhy. 1760' - 1795'.  
5 1/2" at 3873' with 200 sxs.

Ordered 230 sxs 60/40 pozmix - 10% gel - 500# hulls. - 18 sxs gel.

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 17 1997  
09-17-1997  
CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour: 1:00 P.M., Day: 11, Month: September, Year: 1997

Actual plugging report: Mercury Wireline perforated 1780' - 1050'. Fluid level 1100'.  
Allied pumped 40 sxs with 200# hulls - 18 sxs gel, followed with 125 sxs and 100# hulls.  
Squeezed at Max. P.S.I. 2000#. S.I.P. 1000#. Pumped 40 sxs down 8 5/8" Max. P.S.I. 300#.  
S.I.P. 100#.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING .  
Anhy.plug: YES  NO \_\_\_\_\_  
Dakota plug: YES , NO \_\_\_\_\_  
Elevation: 2239 GL

I did  / did not  observe the plugging.

*Richard Williams*  
(agent)

DATE 9-23-97

INV. NO. 49075