

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01925-00-00
Spot: SWSW Sec/Twnshp/Rge: 11-9S-21W
660 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: DAVIGNON Well Number: 1
County: GRAHAM Total Vertical Depth: 3762 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Production Casing Size: 5.5 feet: 3736
Surface Casing Size: 10.75 feet: 279

8122²⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2003 8:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-7202

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel with 300# hulls.
Bad casing from 600' - 725'.
Bridge at 1500' - washed to 1720' - lost circulation - mud up.
Still unable to get below 1720'.
Dakota 688' - 988' - Anhy. 1720' - 1760'. - Fluid level at surface.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/21/2003 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1700'.
Allied pumped 160 sxs 60/40 pozmix - 10% gel - cement circulated.
PTOH. Allied squeezed with 100 sxs cement with 300# hulls.
Max. P.S.I. 300#. S.I.P. 0#.
Hooked up to backside. Allied pumped 75 sxs cement.
Max. P.S.I. 500#. S.I.P. 100#.
Checked 5 1/2" casing cement down 300'.
Will top off at later date.
06-06-2003 - Topped off with 7 yards Redi-Mix (450').

RECEIVED
JUN 09 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 6-10-03
INV. NO. 2003061632

Form CP-2/3

JUN 06 2003

BARNSDALL OIL CO

#1 DAVIGNAN

11-9-21W
C-SW-SW

Contr.

GRAHAM

Count

Fr. 2268

Comm 8-19-42

Comp 9-30-42

1F

761 BORD

Top	Depth	Datum
ANH	1720	
ARB	3736	
TD	3762	

Casing
10" 279
5" 6736

Pump 22 BOPH
1/3000
Pump 113 PO/8 hrs

87880
17300
11300
1100

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS



Handwritten notes on the left margin, including "30300" and "11000".

Handwritten number "1100" in the top right corner.